

## QUOTATION SCHEDULE

### Estimate for the BC Overlay works at TCRIP Corridors.

Sl. No	Description	Unit	Quantity	Rate	Amount
A	<b>BC Overlay-(Attakulangara-Enchakkal,Nalumukku-Sreekandeswaram-Choorakattupalayam,Pattoor-Vanchiyoor-Old Collectrate roads)</b>				
1	Providing and applying tack coat with bitumen emulsion (RS) using emulsion pressure distributor at the rate of 0.20 - 0.30 kg per sqm on the prepared bituminous surface cleaned with mechanical broom.	m <sup>2</sup>	<b>40380.00</b>		
2	Providing and laying bituminous concrete with 80-100 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder (VG-30) @5.4% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade,level and allignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No.507 complete in all respects For grading - II (13.2 mm nominal size) .)	m <sup>3</sup>	<b>1354.00</b>		
3	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads on Bituminous Surface @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.	m <sup>2</sup>	<b>1050.00</b>		
	<b>GRAND TOTAL</b>				

I hereby agree to execute the above work at the above quoted rates.

  
Chief Executive Officer

Contractor