

KERALA ROAD FUND BOARD, THIRUVANANTHAPURAM
QUOTATION SCHEDULE

Estimate PAC - Rs. 3, 47,308.00

Name of Work:- Thiruvananthapuram City Road Improvement Project – Providing additional Safety measures in stretch between Chakkai ITI Junction to Shanghumugham Junction.

Quotation No:- 331/AEE/KRFB/2014-18

Quotation Date:- 28/11/2018

Sl. No.	Qty	Description of Works	Unit	Rate		Rate in Words	Amount
				Rs.	Ps.		
1.	16 Nos	Providing and erecting retro-reflectorised Object Hazard Marker 300mm x 900mm Providing and erecting retro-reflectorised Object Hazard Marker sign with 07 years warranty, manufactured as per IRC 67 USING Type IV ASTM D 4956-09 micro prismatic retro reflective sheeting fixed over aluminium sheeting, 2 mm thick / aluminium composit material sheeting 4 mm thick with suitable back support frame and supported on a mild steel angle iron post 75mmx75mmx6mm, firmly fixed 30cm above ground level by means of properly designed foundation with M 15 grade cement concrete 30cmx30x45cm, 45cm below ground level including painting all non-reflective faces with epoxy paint 2 coats over	Each	2548	70	(Rupees Two Thousand five hundred forty eight and paise Seventy)	40,779.20

Contractor

General Manager

		epoxy primer as per approved drawing and clause 801. (55.10.1)					
2.	514 Nos.	Providing and fixing of median marker made of tough, high impact resistant, injection-molded, thermoplastic body having a minimum Notched Izod Impact strength value of 600J/m at room temperature, when tested accordance with ASTM D256 and shall retain at least 70% of this value when subjected to accelerated weathering for 1000hrs as per ASTM G155 or UL 746C. The Median marker shall have, fluorescent yellow color retro-reflective sheeting min 10cmx10cm/10cm dia size with reflectivity values as per IRC:67 and ASTM D4956 type XI specifications , edge protected with no exposed edges to prevent edge lifting, vandalism, sheeting damage, etc. and fixed by a combination of epoxy adhesive and anchoring and placing at 3m intervals (55.12)	Each	596	36	(Rupees Five Hundred Ninety Six and Paise Thirty Six)	3,06,529.04

Estimate PAC - Rs. 3,47,308.00

QUOTED RATE OF CONTRACTOR

I/We agreed to undertake to execute the work at estimate rate below/above estimate rate less cost of departmental materials and hire charges of departmental tools and plants.

Contractor


General Manager

I/We also agreed that the tender excess/deduction may be calculate after deducting the cost of all departmental materials and hire charges of all tools and plants on the total amount of the works out at the rates given in the schedule attached to the tender/quotation notification.

Signature:

Name and Address of the Contractor:

Contractor


General Manager